






- A. (2) 3" PVC water outlets. One on each side of the start tub.
B. Flume Support Brackets (3) Recommended for use with 12" Concrete Columns (Columns are Not Provided)
C. Elevation @ Pool Coping 1'-0" Where Slide Crosses Coping. Recommend 5' Min. Clearance on either Side of Pool Exit.

Min. Slide Exit Splashdown Envelope: Min 10' Width x 14' Length. Min Water Depth 42" Recommend 72" for Large Slides and Steeper Versions

Slide Views				
Installation Drawing				
Paradise Slides, Inc.				
243 Singing Tree Ln, Cleveland GA 30528				
Flume Type: 32" Open Flume		Recommended GPM: 200 GPM		Ride Length: 32.30'
Drawing Scale: 1/4"=1'-0"		Drawn By: Tim		Slope: 27.68%
Date: March 25, 2026		Model # PS32T5R-S		Sheet # PS32T5R