





- A. (2) 3" PVC water outlets. One on each side of the start tub.
 B. Flume Support Brackets (5) Recommended for use with 12" Concrete Columns (Columns are Not Provided)
 C. Elevation @ Pool Coping 1'-0" Where Slide Crosses Coping. Recommend 5' Min. Clearance on either Side of Pool Exit.

Min. Slide Exit Splashdown Envelope: Min 10' Width x 14' Length. Min Water Depth 42" Recommend 72" for Large Slides and Steeper Versions

Slide Views Installation Drawing

Paradise Slides, Inc.

243 Singing Tree Ln, Cleveland GA 30528

Flume Type:	32" Open Flume	Recommended GPM:	200 GPM	Ride Length:	49.53'
Drawing Scale:	3/16"=1'-0"	Drawn By:	Tim	Slope:	21.47%
Date:	April 02, 2026	Model #	PS50L-C		



Sheet #

PS50L